

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer

Schedule-B


NAME OF WORK: Constructin of RCC drains in Vishweshwaraiah road and other roads in ward no. 13 Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rate quoted by Contractor Smt.MANJULA K	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods Complete Asper the Directon Of Enggineer -in-charge of the work	CUM	252	175.96	Rupees One Hundred Seventy Five and Ninety Six Paise Only
2	Removing B S Slab Drain And Stacking Asper the Directon Of Enggineer -in-charge of the work	SQM	510.3	65.72	Rupees Sixty Five and Seventy Two Paise Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	45.03	4443.52	Rupees Four Thousand Four Hundred Forty Three and Fifty Two Paise Only
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	7.23	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only

Manjula K.
Signautre of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing As per the Director Of Engineer -in-charge of the work	CUM	117.18	5874.52	Rupees Five Thousand Eight Hundred Seventy Four and Fifty Two Paise Only
6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour As per the Director Of Engineer -in-charge of the work	SQM	907.2	310.58	Rupees Three Hundred Ten and Fifty Eight Paise Only
7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery As per the Director Of Engineer -in-charge of the work	Tonne	6.44	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three and Forty Two Paise Only
8	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & As per the Director Of Engineer -in-charge of the work	SQM	8.64	1680.0	Rupees One Thousand Six Hundred Eighty Only


Signature of the Contractor


Executive Engineer,
Dasarahalli Division,

Executive Engineer
Dasarahalli Division